

308 Evergreens Scope

Objective:

Construct a two-story addition approximately 30' x 10' to include basement-level storage space and second-floor expansion

of the primary bedroom, master bathroom, and walk-in closet. Work includes structural integration, foundation system,

framing, roofing, exterior finishes, interior finishes, and full mechanical, electrical, and plumbing systems per provided

drawings and field verification.

General Conditions & Permitting:

Contractor to obtain required permits and coordinate inspections per local jurisdiction.

All work to comply with IRC 2018 and NEC requirements.

Contractor to verify all existing conditions, dimensions, elevations, and tie-in points prior to construction.

Any discrepancies between plans and field conditions will be addressed via change order.

Assumes standard soil conditions. Rock excavation, unsuitable soils, or additional structural requirements are not included

and will be addressed via change order.

Assumes standard framing conditions within existing walls; concealed conditions including wiring, plumbing, or structural

irregularities encountered during demolition will be addressed via change order.

Assumes standard site access for equipment, material staging, and construction operations.

Pre-Construction & Design Phase:

Complete site verification and coordination with provided plans.

Coordinate and complete septic inspection with TDEC.

Determine feasibility of relocating septic system or installing new septic tank and leach field.

Evaluate installation of grinder pump system to connect to available sewer line.

Costs associated with septic relocation, replacement, or grinder system are not included and will be addressed via change

order.

Selective Demolition & Site Work:

Saw cut and remove portions of existing concrete walkway as required.

Remove designated railroad ties and site obstructions.

Excavate for footing and slab system.

Relocate existing heat pump and electrical disconnect.

Extend existing gas water heater vent through new roof system per code requirements.

Provide debris removal and disposal including multiple dump runs.

Foundation & Slab System:

Install continuous 12" x 12" concrete footings around addition perimeter.

Install 4" gravel base below slab.

Install vapor barrier over gravel base.

Install reinforcement (rebar or wire mesh) within slab.

Pour 4" concrete slab with smooth finish.

No CMU or full-height foundation wall system included or anticipated to be needed at this time.

Framing – Structural & Floor System:

Frame basement-level walls using 2x4 lumber at 16" O.C.

Frame floor system above using dimensional lumber or engineered members sized per span and loading requirements.

Install subfloor glued and fastened.

Install (1) engineered LVL beam (3-ply 14") spanning approx. 15'-6" to open existing load-bearing wall including temporary shoring.

Frame all exterior and interior walls using 2x4 lumber at 16" O.C.

Frame (1) future elevator shaft approximately 4' x 4'. Elevator system not included.

Roof System:

Construct new gable roof system (truss or rafter framed, determined during design phase).

Roof pitch approx. 3/12 tying into existing 6/12 roof system.

Install architectural asphalt shingle roofing system most similar to existing.

Install synthetic underlayment, drip edge, flashing, and ridge vent.

Install fascia board, fascia metal, vinyl soffit, and seamless gutters.

Temporary dry-in measures will be installed

Roof tie-in assumes standard integration; additional structural modifications not included.

Exterior Finishes:

Install sheathing and WRB.

Install vinyl siding to match existing as closely as possible.

Install (4) windows including (3) 36" x 60" and (1) transom window.

Install up to (1) new exterior door.

Seal all penetrations and integrate flashing systems.

Exterior finishes to be most similar to existing; exact match not guaranteed.

Electrical (NEC):

Install (1) new 100-amp subpanel.

Install full electrical rough-in and trim-out.

Install approximately (12) recessed lights. Budget \$25 each.

Install (2) vanity light fixtures.

Install (1) vent fan/light combo in bathroom.

Install (1) outlet in upstairs storage.

Install outlets in basement storage per IRC requirements.

Install (3) outlets in master closet.

Relocate (1) existing switch in hallway including drywall patch, priming, and painting.

Install dimmer switches at bedroom and bathroom lighting.

Install standard outlets, switches, and cover plates.

Install GFCI/AFCI protection per code.

Install (1) dedicated 120V, 30A circuit for future elevator.

Assumes existing main electrical service can support new subpanel.

Plumbing:

Install full plumbing rough-in including supply, waste, and vent systems.

Install quarter-turn shutoff valves at all fixtures.

Install master bathroom plumbing including:

(2) lavatory supplies and drains

(1) toilet flange and supply

(1) custom shower with dual valve diverter system

Install washer and dryer relocation including water, drain, and roof venting.

Extend vent stacks through roof as required.

Assumes existing sewer/septic system has adequate capacity.

HVAC:

Install (1) ductless mini-split system. Budget \$2,500.

Relocate existing HVAC components as required.

Final system sizing subject to load calculation.

Insulation & Air Sealing:

Install R13 insulation in exterior walls.

Install R30 insulation in attic/roof system.

Install R30 insulation in floor system between basement and living space.

Seal all penetrations for air control.

Interior Finishes – General:

Install drywall on walls and ceilings where demoed. Apply 3 coats of drywall compound, sanded, ready for paint (Level 3 finish).

Apply primer and (2) coats of finish paint.

Install LVT flooring throughout designated areas. Budget \$3.00/sqft.

Install baseboard: 5-1/4" MDF or finger-jointed pine.

Install casing: 2-1/4" profile.

Install trim, caulk, fill, sand, and paint.

Interior Doors:

Provide and install (4) interior doors total.

Assume (1) pre-hung interior doors and (2) pocket door systems.

Final locations and types to be confirmed during design phase.

Master Bathroom:

Construct custom tile shower approx. 7' x 4'.

Install waterproofing system, tile walls, and mosaic tile floor.

Install shower niche and bench.

Install dual valve diverter system.

Install 72" double vanity.

Install (2) faucets, (2) mirrors, and (2) light fixtures.

Install commode.

Install exhaust fan/light combo vented to exterior.

Primary Bedroom Remodel (~12'5" x 16'):

Modify framing as required.

Install drywall where affected and apply Level 3 finish.

Prime and paint entire room.

Install new LVT flooring.

Install full trim package.

Basement Storage Finish:

Frame and drywall walls.

Apply Level 3 finish and paint.

Install lighting fixture.

Concrete floor remains unfinished.

Existing Hall Bathroom Modification:

Remove existing window and frame opening.

Install insulation, drywall, and finish.

Remove tub/shower combo. Budget \$1,000 Allowance for pan and walls.

Install acrylic shower system.

Reuse existing valve and trim.

Install PVC trim.

Perform minor patching and repaint affected areas.

Water Management:

Does not include French drains, foundation waterproofing, or drainage improvements unless specified.

Elevator Shaft:

Framing only, and rough-in electrical for 30 amp circuit run from sub panel.

Will coordinate with elevator company (101 Mobility preferred) if requested by homeowner.

Cleanup & Closeout:

Remove debris and construction materials.

Perform final cleaning.

Coordinate inspections.

Material Allowance Schedule:

LVT Flooring: \$3.00/sqft

Windows: \$300 each

Interior Doors: \$250 each

Pocket Door Systems: \$400 each

Recessed Lights: \$25 each, up to 18 fixtures.

Vanity (72"): \$1,000

Faucets: \$150 each

Vanity Lights: \$100 each

Commode: \$250

Shower Valve & Trim: \$250

Tile (Walls): \$3.00/sqft

Tile (Floor Mosaic): \$6.00/sqft

Waterproofing/Setting Materials: \$500

Mirrors: \$150 each

Mini Split: \$2,500

Exterior Door: \$500

Guest Bath Shower system pan and walls: \$1,000

Total Investment: \$173,850

Optional Package – Closet & Cabinet System:

Design and installation of custom shelving, rods, and closet organization system.

Allowance: \$7,000. (labor and materials)

Optional Package – Tankless Water Heater:

Remove existing water heater and install tankless system including venting and connections.

Allowance: \$6,500 (labor and materials)

Utility upgrades not included.

Rates:

General Hourly rate: \$70/hr. (All project related work is billed at this rate, with adjustments for the differentials listed below)

Teamlead Differential: +\$15/hr.

Electrical and HVAC Work: +\$30/hr.

Plumbing Work: +\$40/hr.

All materials, consumables, permits, and other related hard costs will be at our discounted cost +15%

Subcontractors at cost + 30% (if applicable)

Debris removal using 7' x 14' dump trailer is \$450 per removal

Backhoe Usage: \$1,100/wk.

Once you are ready to move forward, we can schedule your project upon receipt of a signed agreement and a \$20,000

deposit. After work begins, invoicing will occur weekly for work completed during the prior week. Invoices are due upon

receipt, with any remaining balance due at project completion.

We take pride in managing projects from start to finish and standing behind the work performed. Seeing the transformation

from before to after - and knowing it adds lasting value and enjoyment to your home - is what makes this work meaningful

for our entire team. We look forward to the opportunity to complete your project and deliver a result you can feel confident

about for years to come.