



Tri-Cities Remodeling Company

328 E Elk Ave Ste 2a • Elizabethton, TN 37643-3351 • Phone: 423-796-3624
www.tricitiesremodelingco.com • TN License # 80259

Wayne Simons
Phone: 9515453667

Job Address:
308 Evergreen St
Church Hill, TN 37642

Print Date: 4-6-2026

Proposal for 308 Evergreen St - Addition

Thank you for inviting us to your home to discuss your Addition project.

Tri-Cities Remodeling & Construction Company is a licensed general contracting firm in the State of Tennessee, including electrical, plumbing, and HVAC work. We manage the entire construction process under one contract, with clear responsibility from start to finish.

We operate with a large, full-time, year-round in-house team, supported by a small group of carefully vetted specialty trade partners when appropriate. Regardless of who performs a specific task, all work is coordinated, supervised, and fully warranted by our company. You always have a single point of accountability - us.

Once work begins, you can expect a consistent professional presence on your project. We document progress daily with photos and notes uploaded to our project management system. You will have full access through a mobile app or web portal, allowing you to see real-time updates, daily activity, and overall progress. We use this system because it creates clarity, reduces misunderstandings, and produces better outcomes for everyone involved.

Our estimates are intentionally detailed and comprehensive. Pricing includes all labor, materials, project management, electrical, plumbing, HVAC, permitting, debris removal, equipment usage, and coordination required to complete the work as described. Our goal is to be transparent and realistic up front, so you can make a confident, informed decision without surprises later.

We take pride in doing things differently than the typical contractor model. Our focus is long-term quality, accountability, and standing behind the work we perform - not just during construction, but after the project is complete.

Scope of Work

Objective:

Construct a two-story addition approximately 30' x 10' to include basement-level storage space and second-floor expansion of the primary bedroom, master bathroom, and walk-in closet. Work includes structural integration, foundation system, framing, roofing, exterior finishes, interior finishes, and full mechanical, electrical, and plumbing systems per provided drawings and field verification.

General Conditions & Permitting:

Contractor to obtain required permits and coordinate inspections per local jurisdiction.

All work to comply with IRC 2018 and NEC requirements.

Contractor to verify all existing conditions, dimensions, elevations, and tie-in points prior to construction.

Any discrepancies between plans and field conditions will be addressed via change order.

Assumes standard soil conditions. Rock excavation, unsuitable soils, or additional structural requirements are not included and will be addressed via change order.

Assumes standard framing conditions within existing walls; concealed conditions including wiring, plumbing, or structural irregularities encountered during demolition will be addressed via change order.

Assumes standard site access for equipment, material staging, and construction operations.

Pre-Construction & Design Phase:

Complete site verification and coordination with provided plans.

Coordinate and complete septic inspection with TDEC.

Determine feasibility of relocating septic system or installing new septic tank and leach field.

Evaluate installation of grinder pump system to connect to available sewer line.

Costs associated with septic relocation, replacement, or grinder system are not included and will be addressed via change order.

Selective Demolition & Site Work:

Saw cut and remove portions of existing concrete walkway as required.

Remove designated railroad ties and site obstructions.

Excavate for footing and slab system.

Relocate existing heat pump and electrical disconnect.

Extend existing gas water heater vent through new roof system per code requirements.

Provide debris removal and disposal including multiple dump runs.

Foundation & Slab System:

Install continuous 12" x 12" concrete footings around addition perimeter.

Install 4" gravel base below slab.

Install vapor barrier over gravel base.

Install reinforcement (rebar or wire mesh) within slab.

Pour 4" concrete slab with smooth finish.

No CMU or full-height foundation wall system included or anticipated to be needed at this time.

Framing – Structural & Floor System:

Frame basement-level walls using 2x4 lumber at 16" O.C.

Frame floor system above using dimensional lumber or engineered members sized per span and loading requirements.

Install subfloor glued and fastened.

Install (1) engineered LVL beam (3-ply 14") spanning approx. 15'-6" to open existing load-bearing wall including temporary shoring.

Frame all exterior and interior walls using 2x4 lumber at 16" O.C.

Frame (1) future elevator shaft approximately 4' x 4'. Elevator system not included.

Roof System:

Construct new gable roof system (truss or rafter framed, determined during design phase).

Roof pitch approx. 3/12 tying into existing 6/12 roof system.

Install architectural asphalt shingle roofing system most similar to existing.

Install synthetic underlayment, drip edge, flashing, and ridge vent.

Install fascia board, fascia metal, vinyl soffit, and seamless gutters.

Temporary dry-in measures will be installed

Roof tie-in assumes standard integration; additional structural modifications not included.

Exterior Finishes:

Install sheathing and WRB.

Install vinyl siding to match existing as closely as possible.

Install (4) windows including (3) 36" x 60" and (1) transom window.

Install up to (1) new exterior door.

Seal all penetrations and integrate flashing systems.

Exterior finishes to be most similar to existing; exact match not guaranteed.

Electrical (NEC):

Install (1) new 100-amp subpanel.

Install full electrical rough-in and trim-out.

Install approximately (12) recessed lights. Budget \$25 each.

Install (2) vanity light fixtures.

Install (1) vent fan/light combo in bathroom.

Install (1) outlet in upstairs storage.

Install outlets in basement storage per IRC requirements.

Install (3) outlets in master closet.

Relocate (1) existing switch in hallway including drywall patch, priming, and painting.

Install dimmer switches at bedroom and bathroom lighting.

Install standard outlets, switches, and cover plates.

Install GFCI/AFCI protection per code.

Install (1) dedicated 120V, 30A circuit for future elevator.

Assumes existing main electrical service can support new subpanel.

Plumbing:

Install full plumbing rough-in including supply, waste, and vent systems.

Install quarter-turn shutoff valves at all fixtures.

Install master bathroom plumbing including:

(2) lavatory supplies and drains

(1) toilet flange and supply

(1) custom shower with dual valve diverter system

Install washer and dryer relocation including water, drain, and roof venting.

Extend vent stacks through roof as required.

Assumes existing sewer/septic system has adequate capacity.

HVAC:

Install (1) ductless mini-split system. Budget \$2,500.

Relocate existing HVAC components as required.

Final system sizing subject to load calculation.

Insulation & Air Sealing:

Install R13 insulation in exterior walls.

Install R30 insulation in attic/roof system.

Install R30 insulation in floor system between basement and living space.

Seal all penetrations for air control.

Interior Finishes – General:

Install drywall on walls and ceilings where demoed. Apply 3 coats of drywall compound, sanded, ready for paint (Level 3 finish).

Apply primer and (2) coats of finish paint.

Install LVT flooring throughout designated areas. Budget \$3.00/sqft.

Install baseboard: 5-1/4" MDF or finger-jointed pine.

Install casing: 2-1/4" profile.

Install trim, caulk, fill, sand, and paint.

Interior Doors:

Provide and install (4) interior doors total.

Assume (1) pre-hung interior doors and (2) pocket door systems.

Final locations and types to be confirmed during design phase.

Master Bathroom:

Construct custom tile shower approx. 7' x 4'.

Install waterproofing system, tile walls, and mosaic tile floor.

Install shower niche and bench.

Install dual valve diverter system.

Install 72" double vanity.

Install (2) faucets, (2) mirrors, and (2) light fixtures.

Install commode.

Install exhaust fan/light combo vented to exterior.

Primary Bedroom Remodel (~12'5" x 16'):

Modify framing as required.

Install drywall where affected and apply Level 3 finish.

Prime and paint entire room.

Install new LVT flooring.

Install full trim package.

Basement Storage Finish:

Frame and drywall walls.

Apply Level 3 finish and paint.

Install lighting fixture.

Concrete floor remains unfinished.

Existing Hall Bathroom Modification:

- Remove existing window and frame opening.
- Install insulation, drywall, and finish.
- Remove tub/shower combo. Budget \$1,000 Allowance for pan and walls.
- Install acrylic shower system.
- Reuse existing valve and trim.
- Install PVC trim.
- Perform minor patching and repaint affected areas.

Water Management:

Does not include French drains, foundation waterproofing, or drainage improvements unless specified.

Elevator Shaft:

- Framing only, and rough-in electrical for 30 amp circuit run from sub panel.
- Will coordinate with elevator company (101 Mobility preferred) if requested by homeowner.

Cleanup & Closeout:

- Remove debris and construction materials.
- Perform final cleaning.
- Coordinate inspections.

Material Allowance Schedule:

- LVT Flooring: \$3.00/sqft
- Windows: \$300 each
- Interior Doors: \$250 each
- Pocket Door Systems: \$400 each
- Recessed Lights: \$25 each, up to 18 fixtures.
- Vanity (72"): \$1,000
- Faucets: \$150 each
- Vanity Lights: \$100 each
- Commode: \$250
- Shower Valve & Trim: \$250
- Tile (Walls): \$3.00/sqft
- Tile (Floor Mosaic): \$6.00/sqft
- Waterproofing/Setting Materials: \$500
- Mirrors: \$150 each
- Mini Split: \$2,500
- Exterior Door: \$500
- Guest Bath Shower system pan and walls: \$1,000
- Total Investment: \$173,850**

Items	Description	Price
Addition	Addition Project as Listed Above	\$173,850.00
OPTION - Closet Finish Package - \$7,000	Optional Package as Listed Below	\$0.00
OPTION - Tankless Water Heater - \$6,500	Optional Package as Listed Below	\$0.00

Total Price: \$173,850.00

Optional Package – Closet & Cabinet System:

Design and installation of custom shelving, rods, and closet organization system.
Allowance: \$7,000. (labor and materials)

Optional Package – Tankless Water Heater:

Remove existing water heater and install tankless system including venting and connections.
Allowance: \$6,500 (labor and materials)
Utility upgrades not included.

Rates:

General Hourly rate: \$70/hr. (All project related work is billed at this rate, with adjustments for the differentials listed below)
Teamlead Differential: +\$15/hr.
Electrical and HVAC Work: +\$30/hr.
Plumbing Work: +\$40/hr.
All materials, consumables, permits, and other related hard costs will be at our discounted cost +15%
Subcontractors at cost + 30% (if applicable)
Debris removal using 7' x 14' dump trailer is \$450 per removal
Backhoe Usage: \$1,100/wk.

Once you are ready to move forward, we can schedule your project upon receipt of a signed agreement and a **\$20,000 deposit**. After work begins, invoicing will occur weekly for work completed during the prior week. Invoices are due upon receipt, with any remaining balance due at project completion.

We take pride in managing projects from start to finish and standing behind the work performed. Seeing the transformation from before to after - and knowing it adds lasting value and enjoyment to your home - is what makes this work meaningful for our entire team. We look forward to the opportunity to complete your project and deliver a result you can feel confident about for years to come.

If you have any questions or would like to review the scope together before moving forward, we’re happy to walk through it with you.

Will Fallon
423-796-3624

I confirm that my electronic signature acknowledges that I agree to this proposal or estimate as listed.

Attach

Signature:

Date:

Apr 6, 2026, 2:49 PM

Builder Approved by:

Will Fallon