

Approved by Will Fallon on Jul 28, 2026

Approved

**Tri-Cities Remodeling Company**

328 E Elk Ave Ste 2a • Elizabethton, TN 37643-3351 • Phone: 423-512-1993

Sarah Lawson | Phone: +1 (423) 291-0557

Job Address:
205 Pawnee Street
Johnson City, TN 37604

Print Date: 9-8-2026

Proposal for 205 Pawnee Street - Deck Building

Thank you for inviting us to your home to discuss your patio and roof project.

Tri-Cities Remodeling & Construction Company is a licensed general contracting firm in the State of Tennessee, including electrical, plumbing, and HVAC work. We manage the entire construction process under one contract, with clear responsibility from start to finish.

We operate with a large, full-time, year-round in-house team, supported by a small group of carefully vetted specialty trade partners when appropriate. Regardless of who performs a specific task, all work is coordinated, supervised, and fully warranted by our company. You always have a single point of accountability - us.

Once work begins, you can expect a consistent professional presence on your project. We document progress daily with photos and notes uploaded to our project management system. You will have full access through a mobile app or web portal, allowing you to see real-time updates, daily activity, and overall progress. We use this system because it creates clarity, reduces misunderstandings, and produces better outcomes for everyone involved.

Our estimates are intentionally detailed and comprehensive. Pricing includes all labor, materials, project management, electrical, plumbing, HVAC, permitting, debris removal, equipment usage, and coordination required to complete the work as described. Our goal is to be transparent and realistic up front, so you can make a confident, informed decision without surprises later.

We take pride in doing things differently than the typical contractor model. Our focus is long-term quality, accountability, and standing behind the work we perform - not just during construction, but after the project is complete.

Scope of Work:**Demolition:**

Demolition and removal of current pavers (approx. 12.5' x 23.5' area)

Demolition and removal of current fire pit (Cut approx 3'x 3' area of concrete)

Tri Cities Remodeling and Construction Co. will remove and properly dispose of all debris and construction waste generated during both the demolition and construction phases.

Tri Cities Remodeling and Construction Co. will provide a 12-yard dumpster on-site for the duration of the project, ensuring organized, and efficient disposal of all demolition and construction debris.

This quote includes allowance for (1) dump run

New Concrete

Excavate approx 12.5' x 23.5' area for new concrete patio

Install gravel base approx (4) yards
Includes form work, and concrete placement
Install standard reinforcement as required per IRC code
Pour 4" concrete patio
Provide broom finish surface
Cut control joints at practical spacing as required per IRC code
Minor hand grading at edges included.
Decorative stamping, coloring, and retaining work excluded unless added by change order
Pour new 4" concrete to fill 3' x 3' area from removed fire pit

Roof Structure:

Construct a shed-style roof system over approximately 12.5' x 23.5' section of new concrete, tying into the existing roof structure as required.
Frame roof using rafters sized in accordance with span and load requirements.
Install structural ledger and/or beam connection to existing home with proper flashing to ensure a watertight integration.
Install vertical support posts, integrated with existing deck framing, to adequately support roof loads. Install roof sheathing over framed rafters.
Install synthetic roof underlayment over sheathing.
Install asphalt shingle roofing system, selected to closely match existing roof color and style.
Install metal flashing at all roof-to-wall intersections, valleys, and penetrations to prevent water intrusion.
Ensure proper roof pitch and drainage directing water away from the structure.

Screened Enclosure:

Frame wall sections as required to accommodate screened enclosure.
Build 2' tall knee-wall on all perimeter walls with white vinyl finish
Install screen framing system between posts and along perimeter openings.
Install durable screening material, securely fastened and properly tensioned to prevent sagging.
Install trim boards to secure and finish all screened sections for a clean, finished appearance.
Frame (1) screen door opening
Install (1) screen door including hardware. Budget \$125 retail cost per door and hardware set

Wood-Burning Outdoor Fireplace:

Construct wood-burning outdoor fireplace on patio, approximately 72" wide, with final height and configuration determined by selected fireplace design, required flue height, roof/ceiling clearance, and applicable code requirements.
Fireplace to be constructed as a code-compliant wood-burning masonry or framed fireplace system using approved fire-rated materials, firebox, smoke chamber, flue liner, chimney system, and required clearances from combustible materials.
Install proper footing or structural support for fireplace assembly as required based on final fireplace design, weight, patio conditions, and code requirements.
Install firebox, throat, smoke shelf/smoke chamber, and flue/chimney system per manufacturer specifications and applicable IRC/local code requirements.
Install chimney/flue extension to required termination height above roofline/adjacent structures as required by code and final site conditions.
Install spark arrestor, chimney cap, and required flashing/weatherproofing at any roof or ceiling penetrations.
Install fire-rated cement board, masonry backer, or approved substrate as required for selected fireplace system and exterior finish material.
Install stone or tile veneer product of customer selection using approved mortar/thin set system suitable for exterior/fireplace conditions. Budget up to **\$5/sqft retail cost of stone or tile veneer product.**
Install hearth at floor height or with slight raised lip as required by design and code. Hearth material to be customer selected and installed using approved fire-rated materials. Budget up to **\$5/sqft retail cost of hearth product.**
Install non-combustible mantel or wood mantel only if clearances from firebox opening meet manufacturer and code requirements. Budget up to **\$1,000 retail cost of mantel and associated hardware.**
Electrical circuit for electric fireplace is removed from this scope.
Electric fireplace fixture allowance is removed from this scope.
Final fireplace design, flue/chimney routing, termination height, and material requirements are subject to code requirements, manufacturer specifications, field conditions, and inspection authority approval.

Total Investment: \$57,745

Items	Description	Price
Deck	Build Deck as Above	\$57,745.00

Subtotal: \$57,745.00

Tax: \$0.00

Total price: \$57,745.00

Once you are ready to move forward, we can schedule your project upon receipt of a signed agreement and a \$10,000 deposit. After work begins, invoicing will occur weekly for work completed during the prior week. Invoices are due upon receipt, with any remaining balance due at project completion.

We take pride in managing projects from start to finish and standing behind the work performed. Seeing the transformation from before to after - and knowing it adds lasting value and enjoyment to your home - is what makes this work meaningful for our entire team. We look forward to the opportunity to complete your project and deliver a result you can feel confident about for years to come.

If you have any questions or would like to review the scope together before moving forward, we're happy to walk through it with you.

Patrick Fallon
423-656-5294
Patrick.Fallon@TCRandC.com

I confirm that my action here represents my electronic signature and is binding and agree to the Terms and Conditions.

Approvals

 Will Fallon
Jul 28, 2026

Internally approved

Patrick has paper signed copy.

 Sarah Lawson

Not required