

Approved by Will Fallon on Apr 9, 2026

Approved

**Tri-Cities Remodeling Company**

328 E Elk Ave Ste 2a • Elizabethton, TN 37643-3351 • Phone: 423-512-1993
tricitiesremodelingco.com • TN License # 80259

Shane Lavinder
Phone: 423-863-9256

Job Address:
333 Toy Crawford Rd
Kingsport, TN 37660

Print Date: 9-9-2026

Proposal for 333 Toy Crawford Rd - Addition Updated: Footers and Roof Repair

Thank you for inviting us to your home to discuss your Addition project.

Tri-Cities Remodeling & Construction Company is a licensed general contracting firm in the State of Tennessee, including electrical, plumbing, and HVAC work. We manage the entire construction process under one contract, with clear responsibility from start to finish.

We operate with a large, full-time, year-round in-house team, supported by a small group of carefully vetted specialty trade partners when appropriate. Regardless of who performs a specific task, all work is coordinated, supervised, and fully warranted by our company. You always have a single point of accountability - us.

Once work begins, you can expect a consistent professional presence on your project. We document progress daily with photos and notes uploaded to our project management system. You will have full access through a mobile app or web portal, allowing you to see real-time updates, daily activity, and overall progress. We use this system because it creates clarity, reduces misunderstandings, and produces better outcomes for everyone involved.

Our estimates are intentionally detailed and comprehensive. Pricing includes all labor, materials, project management, electrical, plumbing, HVAC, permitting, debris removal, equipment usage, and coordination required to complete the work as described. Our goal is to be transparent and realistic up front, so you can make a confident, informed decision without surprises later.

We take pride in doing things differently than the typical contractor model. Our focus is long-term quality, accountability, and standing behind the work we perform - not just during construction, but after the project is complete.

Scope of Work – Elevated Sunroom Addition Replacement (43' x 10')

Objective:

Demolish and replace an existing elevated second-story sunroom structure due to improper original construction. Work includes selective structural demolition while maintaining temporary roof support, installation of a new code-compliant floor and wall system, exterior enclosure, mechanical/electrical systems, and interior drywall-ready finishes.

General Conditions, Protection & Structural Support:

Install temporary shoring and structural support system to maintain existing shed roof during demolition and reconstruction.

Install jobsite protection at access points and adjacent finishes below work area.

Coordinate all work to meet IRC 2018 and NEC requirements.

Verify existing electrical disconnect condition prior to reuse and modification.

Selective Demolition:

Demolish existing 43' x 10' elevated sunroom including 6x6 posts, floor framing, subfloor, wall framing, windows, and ceiling assemblies.

Remove existing substandard structural components down to bearing points required for new construction.

Preserve existing roof system with temporary support during demolition and rebuild phases.

Dispose of all demolition debris. Budget (3) dump trailer runs.

Foundation, Posts & Beam System:

Install (8) new 6x6 pressure-treated posts.

Cut Concrete footers approx. 12" x 12" x 12" near existing pad.

Install concrete footers at each post location measuring 12" x 12" x 12".

Install post brackets anchored to concrete footers.

Install (1) primary beam approximately 44 LF consisting of (3) ply 2x12 dimensional lumber, fastened per code.

All framing sized and installed per IRC span tables and loading requirements.

Floor System:

Frame new floor system using pressure-treated framing lumber sized per IRC span requirements.

Install subfloor sheathing to IRC requirements, glued and fastened.

Install insulation within floor cavity.

Install vinyl soffit system beneath floor framing to protect against weather and pest intrusion.

Wall Framing & Exterior Envelope:

Frame exterior walls using 2x4 lumber at 16" O.C.

Install exterior wall sheathing.

Install weather-resistant barrier.

Install vinyl lap siding on all exterior wall surfaces. Budget allowance: \$150/square retail cost.

Windows & Exterior Door:

Install up to (6) new vinyl windows, 36" x 60". Budget allowance: \$300 per window retail cost.

Install (1) exterior pre-hung door, 36" x 80", with hardware. Budget allowance: \$500 retail cost.

Roof Integration:

Reintegrate existing shed roof system onto new wall structure.

Install required flashing and tie-ins to maintain weather-tight condition.

Install up to (2) roof patch/repair from previous venting**Electrical (NEC Compliant):**

Modify existing disconnect panel by replacing fuses with breaker configuration to function as subpanel.

Install electrical rough-in for outlets per IRC/NEC spacing requirements.

Install wiring and boxes for (6) flush-mount light fixtures. Budget allowance: \$75 per fixture.

Install wiring and support for (2) ceiling fans. Budget allowance: \$150 per fan.

Install switches and circuits as required.

HVAC:

Install (1) ductless mini-split system sized appropriately for space. Budget allowance: \$2,500 retail cost.

Insulation:

Install batt insulation in all exterior wall cavities.

Install insulation in floor system as specified above.

Drywall:

Install drywall on walls.

Apply 3 coats of drywall compound, sanded, ready for paint (Level 3 finish).

Cleanup & Closeout:

Perform jobsite cleanup.

Remove all construction debris from site.

Materials Allowance Schedule (Retail Cost Basis):

Windows (6): \$300 each = \$1,800

Exterior Door: \$500

Vinyl Siding: \$150/square

Mini-Split System: \$2,500

Light Fixtures (6): \$75 each = \$450

Ceiling Fans (2): \$150 each = \$300

Total Investment: \$66,700

Items	Description	Price
Addition	Addition Project as Listed Above	\$66,700.00
Good Will Discount	Good Will Discount	-\$500.00
OPTION - Brick - \$8,500	Optional Package Listed Below	\$0.00
OPTION - Interior Finish - \$9,500	Optional Package Listed Below	\$0.00

Total Price: \$66,200.00

Optional Packages:

Option 1 – Enhanced Footer & Brick Pier Wrap Package:

Upgrade all (8) post footers from 12" x 12" x 12" to 24" x 24" x 12".

Install brick wrap around all (8) posts from grade to beam height.

Estimated brick quantity: approx. 400–500 bricks total.

Brick allowance: \$0.75 per brick retail cost.

Includes mortar, installation, and finishing.

Total Package: \$8,500

Option 2 – Interior Finish Package:

Install LVP flooring throughout sunroom. Budget allowance: \$3.00/sqft retail cost.

Install baseboard trim throughout perimeter.

Install door casing at exterior door.

Caulk, fill, and sand all trim.

Apply 1 coat primer and 2 coats finish paint to walls and trim.

Total Package: \$9,500

Once you are ready to move forward, we can schedule your project upon receipt of a signed agreement and a **\$15,000 deposit**. After work begins, invoicing will occur weekly for work completed during the prior week. Invoices are due upon receipt, with any remaining balance due at project completion.

We take pride in managing projects from start to finish and standing behind the work performed. Seeing the transformation from before to after - and knowing it adds lasting value and enjoyment to your home - is what makes this work meaningful for our entire team. We look forward to the opportunity to complete your project and deliver a result you can feel confident about for years to come.

If you have any questions or would like to review the scope together before moving forward, we're happy to walk through it with you.

Will Fallon

423-796-3624

I confirm that my electronic signature acknowledges that I agree to this proposal or estimate as listed.

Attach

Signature:

Date:

Apr 9, 2026, 12:38 PM

Builder Approved by:

Will Fallon