

Approved by Patrick Fallon on May 7, 2026

Approved

**Tri-Cities Remodeling Company**

328 E Elk Ave Ste 2a • Elizabethton, TN 37643-3351 • Phone: 423-512-1993
tricitiesremodelingco.com • TN License # 80259

Jeanne Chastain
Phone: 623-451-8785

Job Address:
166 Fairground Lane
Mountain City, TN 37683

Print Date: 8-2-2026

Proposal for 166 Fairground Lane - Four-Season Room (2)

Thank you for inviting us to your home to discuss your Four-Season Room project.

Tri-Cities Remodeling & Construction Company is a licensed general contracting firm in the State of Tennessee, including electrical, plumbing, and HVAC work. We manage the entire construction process under one contract, with clear responsibility from start to finish.

We operate with a large, full-time, year-round in-house team, supported by a small group of carefully vetted specialty trade partners when appropriate. Regardless of who performs a specific task, all work is coordinated, supervised, and fully warranted by our company. You always have a single point of accountability - us.

Once work begins, you can expect a consistent professional presence on your project. We document progress daily with photos and notes uploaded to our project management system. You will have full access through a mobile app or web portal, allowing you to see real-time updates, daily activity, and overall progress. We use this system because it creates clarity, reduces misunderstandings, and produces better outcomes for everyone involved.

Our estimates are intentionally detailed and comprehensive. Pricing includes all labor, materials, project management, electrical, plumbing, HVAC, permitting, debris removal, equipment usage, and coordination required to complete the work as described. Our goal is to be transparent and realistic up front, so you can make a confident, informed decision without surprises later.

We take pride in doing things differently than the typical contractor model. Our focus is long-term quality, accountability, and standing behind the work we perform - not just during construction, but after the project is complete.

Scope of Work:

Objective:

Remove the existing approximately **14' x 16' pressure-treated lumber deck** and construct a new **14' x 16' four-season room addition** with block foundation, lower storage area, exterior storage access, retaining/stairwell walls, new Trex deck, concrete walkway, metal roof system, interior finishes, electrical, subpanel, and mini-split HVAC system.

General Conditions / Planning / Coordination:

Contractor to verify final field measurements, elevations, drainage flow, tie-in conditions, utility locations, framing connections, and finished floor transitions prior to construction.

Contractor to coordinate permit applications and required inspections where applicable.

Contractor to maintain organized jobsite conditions and debris removal during construction.

Concrete, excavation, and structural design assumed standard residential conditions unless hidden conditions are discovered.
Final grade includes seed and straw to immediately disturbed areas

Selective Demolition:

Demolish and remove existing approximately **14' x 16' pressure-treated deck structure**, including decking, railing, stairs if present, framing, posts, and accessible footings as required for new construction.
Remove existing exterior door from home leading onto removed deck.
Dispose of demolition debris offsite.

Post and Beam Foundation:

Excavate up to (6) footers for Post and beam foundation. Minimum 12" x 12" concrete footers.
Pour and finish up to (6) concrete Footers
Install 6x6 post bracket, fastened to concrete per IRC code requirements.
Install PT lumber 6x6 Posts to support 4-Season room.
Install beams sized per IRC code requirements for supporting floor system, LVL's omitted, and may need to be added via change order depending on final engineering.
Install white metal wrap around beams for weather protection.
Install vinyl soffit on bottom of floor framing/insulation to protect from weathering.

Four-Season Room Structure - Approx. 14' x 16':

Frame floor, walls, and roof system above new foundation.
Construct gable roof system tied into existing home where practical.
Install roof sheathing, underlayment, trim, and **metal roofing system**.
Install wall sheathing, and vinyl lap siding
Install soffit, fascia, fascia metal, and seamless gutters on new roof system.
Construct stair system from four-season room level down toward backyard. Up to (6) steps for entire project, includes 4' x 3' concrete landing at the end of the stairs.

Windows / Doors:

Install **(7) new 36" x 60" windows** in four-season room. Allowance based on white vinyl insulated units. Windows to be similar cream color as existing home windows
Install **(2) new 36" exterior doors** for four-season room. One door to new deck and one door to exterior stair access.
Replace existing house rear door with new **36" exterior door** where current deck access exists.
Interior casing / trim style to be standard paint-grade package.

Interior Finishes - Four Season Room:

Install insulation in exterior walls and roof cavities where applicable.
Install drywall on walls and ceilings in four-season room. Apply 3 coats of drywall compound, sanded, ready for paint.
Install LVP flooring throughout four season room.
Install baseboard and standard interior trim package.
Prime-ready trim to be installed
Ceilings to be vaulted with drywall finish

Electrical:

Install new subpanel dedicated to the four season room addition and associated exterior improvements.
Subpanel to serve new recessed lighting, outlets, switches, mini-split system, and related branch circuits for the addition.
Includes feeder wiring from existing main service panel, breakers, grounding/bonding as required, and standard code-compliant installation assuming existing service has adequate capacity. Assumes MC clad wire.
Install wiring and devices for:
(1) switch
(4) recessed lights
(4) outlets
Install dedicated electrical circuiting and disconnect for mini-split system.
All new wiring to be installed per applicable code standards.
Main service upgrades excluded unless required after inspection.

HVAC:

Install one mini-split heating and cooling system sized appropriately for four season room. Allowance based on standard residential

wall-mounted system.

Includes condenser, air handler, lineset, condensate routing, disconnect, and startup.

New Elevated Deck - Approx. 8' x 14':

Construct attached deck adjoining four-season room.

Excavate footers per IRC code requirements.

Pour and finish footers

Install (6x6) post brackets.

Install (6x6) posts.

Attach new ledger board

Install **Trex Enhance decking boards.**

Install **Trex white composite handrail system** at open sides

Framing to include (1) extra post, footer, and brack for hot tub support

Framing to include (1) extra beam for extra support

Concrete Walkway:

Construct new concrete walkway from lower stair area to existing driveway.

Walkway to be approximately **36" wide x 48/LF.**

Includes excavation of topsoil as needed, compacted stone base, formwork, standard reinforcement as required, concrete placement, broom finish surface, and control joints at practical spacing.

Final routing to be field determined based on drainage flow, grade, and tie-in conditions.

Minor hand grading at edges included.

Decorative stamping, coloring, and retaining work excluded unless added by change order

Material Allowance Schedule:

Windows allowance: **\$300 per window**

Exterior doors allowance: **\$500 per door and hardware set**

LVP flooring allowance: **\$3.00/sqft retail**

Mini-split allowance: **\$2,500 retail**

Recessed Lights allowance: **\$25 per fixture**

Ceiling Fan allowance: **\$125 per fixture**

Dump Runs budgeted in 7' x 14' dump trailers: **(2)**

Non-Standard Conditions:

Hidden rot, termite damage, inadequate existing framing, concealed utilities, rock excavation, groundwater intrusion, unsuitable soils, or code-mandated upgrades not visible at time of estimate are excluded and handled by change order if encountered.

Matching existing siding, roofing, masonry, and interior finishes may vary due to age/weathering/discontinued products.

Storage area intended for general household storage use only unless otherwise engineered.

Total Investment: \$76,300

Items	Description	Price
Four-Season Room	Build Four-Season Room as listed above	\$76,300.00
OPTION - Replace Existing Roof - \$27,000	Replace roof as listed below	\$0.00

Total Price: \$76,300.00

Options:

Roof replacement: - \$27,000

- Demo existing shingle roofing system
- Install synthetic underlayment over roof sheathing.
- Install metal roofing system with manufacturer-approved fasteners and closures.
- Install metal flashing at all roof-to-wall intersections and penetrations.
- Ensure proper slope and drainage away from structure.
- Remove up to (1) load of project-related debris removal in 7' x 14' dump trailer

Once you are ready to move forward, we can schedule your project upon receipt of a signed agreement and a \$12,000 deposit. After work begins, invoicing will occur weekly for work completed during the prior week. Invoices are due upon receipt, with any remaining balance due at project completion.

We take pride in managing projects from start to finish and standing behind the work performed. Seeing the transformation from before to after - and knowing it adds lasting value and enjoyment to your home - is what makes this work meaningful for our entire team. We look forward to the opportunity to complete your project and deliver a result you can feel confident about for years to come.

If you have any questions or would like to review the scope together before moving forward, we're happy to walk through it with you.

Patrick Fallon
423-656-5294
Patrick.Fallon@TCRandC.com

I confirm that my electronic signature acknowledges that I agree to this proposal or estimate as listed.

Signature: _____

Date: _____

Print Name: _____